HuBei Petrokh Petroleum Machinery Co., Ltd.

Oil & Gas Petroleum Machinery — Fracturing · Cementing · Acidizing · Workover

Web: https://www.petrokh.net | Email: chinapetroleummachinery@hotmail.com | Jingzhou, Hubei, China

XJ250 Truck-Mounted Workover Rig

Workover & Well Intervention Rig

The XJ250 workover rig contains a single-drum drawworks and a hydraulically lifted double (or single) derrick, and can be fitted with a mud pump circulation system for light drilling and coiled-tubing operations.

Technical Specifications

Model	XJ250 (250 HP / 300 HP class)
Service Depth (2-7/8" UE tubing)	3200 m
Workover Depth (2-7/8" DP)	2000 m
Max. Hook Load	675 kN (151746 lb)
Rated Hook Load	400 kN (89924 lb)
Drawworks	Single drum / double drum (sand reel & bank brake optional)
Drawworks Rated Power	187 kW / 250 HP
Engine Model / Power	CAT C-9, 300 hp (224 kW)
Derrick Height	18 m single / 21 m double
Wireline Diameter	22 mm
Effective Line Quantity	6
Max. Hook Lifting Speed	1.5 m/s
Chassis	Chinese-made 6×4 or 6×6 optional

Typical Applications

- Oil & gas well workover and well intervention
- Tubing / completion running and pulling
- Light drilling and coiled-tubing support

Certification & Testing: API · HSE · ISO 9001:2008 Certified Manufacturer | Established in 2006. This unit is designed and built for oilfield service duty; full factory test reports and configuration data are available on request.